

Quotation



Quote To

Millpack Pty Ltd
Unit 3, 43-45 Lakewood Blvd
CARRUM DOWNS VIC 3201
AUSTRALIA

Ship-to address

Millpack Pty Ltd
Unit 3, 43-45 Lakewood Blvd
CARRUM DOWNS VIC 3201
AUSTRALIA

Quotation No. : 5295
Customer No. : C11243
Date : 28/04/2022
Valid Until : 28/05/2022
Contact Name : [REDACTED]
Contact Phone : [REDACTED]
Contact Mobile : [REDACTED]
Contact Email : [REDACTED]
Page : 1 of 2

Dear John,

In regards to our recent conversation, I am now forwarding the following quotation in response to your inquiry.

Delivery	All items quoted 8-10 Weeks from confirmation of drawing	
Payment Terms	1st	30% deposit on placement of order
	2nd	30% on signing of manufacturing drawings
	3rd	30% on successful factory testing
	Final	10% within 30 days from date of invoice

Note: The first three invoice payments are required within 5 working days from the date of invoice.

Failure to meet the above payment terms as agreed, or prolonged deliberation over drawings will result in a hold being placed on progression of the project.

All prices quoted do not include delivery and are quoted in Australia (AUD) dollars. All quotations will have a validation period of sixty days. All orders received outside this period may be subject to price fluctuations. In the event of the order being cancelled or postponed, funds paid will not be refunded. All deposits have a validation period of 90 days from date of payment, if a project that has been placed on hold is not reinstated within this 90 day period the project will be considered cancelled and all funds paid will be retained by Enmin Vibratory Equipment and can not be used against any future projects.

Total Price \$25,080.00 Price Does not Inc GST or delivery

If you require any additional information or wish to query the current quotation, please do not hesitate to contact me.

Regards

Anthony Gallaher
General Manager
Office Phone: 03 9800 6777
Mobile Phone: 0407 824 642
Email: anthony@enmin.com.au

Quotation



Quote To

Millpack Pty Ltd
Unit 3, 43-45 Lakewood Blvd
CARRUM DOWNS VIC 3201
AUSTRALIA

Ship-to address

Millpack Pty Ltd
Unit 3, 43-45 Lakewood Blvd
CARRUM DOWNS VIC 3201
AUSTRALIA

Quotation No. : 5295
Customer No. : C11243
Date : 28/04/2022
Valid Until : 28/05/2022
Contact Name : [REDACTED]
Contact Phone : [REDACTED]
Contact Mobile : [REDACTED]
Contact Email : [REDACTED]
Page : 2 of 2

Item Name	Quantity	Unit Price	Total AUD
Enmin Electromechanical Screener	1.00	\$ 25,080.00	\$ 25,080.00
Equipment Type	Enmin Electromechanical Feeder		
Equipment Model	EME-S 100-35-B		
Application	Screen Lumps		
Product	Peanut Meal		
Rate Required	60 KG / HR		
Bulk Density	500 KG / m3		
Item 1 Drive	Drive Specification		
- Motor Type	Twin Out Of Balance (URAS)		
- Voltage	415 Volt 50 Hz 3 Phase		
- Qty of Drives	2		
- Motor Position	Underneath		
Item 2 Controls	Fixed Speed		
- Controller Description	Stop Start / Mains isolator		
- Enclosure Rating	IP 66 304 stainless steel		
- Additional	Fitted and wired support frame		
Item 3 Tray Type	Standard / Screener		
- Material	304 Stainless steel		
- Length	1000 mm		
- Width	350 mm		
- Depth	100 mm		
- Finish External	Bead Blasted		
- Finish Internal	General Polish		
- Tray Discharge Type	Straight I		
- Vibration Mounts	304 Stainless Steel		
- Screen Type	Woven Wire		
- Screen Material	304 Stainless Steel		
- Fixing	Rear Tensioned		
Item 4 Support	Mobile / Fixed		
- Material	304 Stainless steel		
- Finish	General Polish		
- Fixing	Articulated Feet / Jacking Feet / Lockable casters		
- Discharge Height	600 mm (Approx)		

Subtotal \$ 25,080.00

Freight \$ 0.00

GST \$ 2,508.00

Total Inc GST \$ 27,588.00